



Guide Specifications

ELITE® SERIES LARGE SPLIT SYSTEM UNITS

ELKP – Heat Pump

R-454B - 60 HZ

March 18, 2024



Note: This Specification is for Lennox Industries **Elite® Series, 6-ton to 10-ton, outdoor heat pump split system** (EL series) units. Revise specification section number and title below to suit project requirements, specification practices and section content. Refer to CSI MasterFormat for other section numbers and titles.

Optional text or text requiring a decision is indicated by bolded brackets []; delete text not required in final copy of specification. Specifier Notes typically precede specification text; delete notes in final copy of specification. Trade/brand names with appropriate symbols typically are used in Specifier Notes; symbols are not used in specification text. Metric conversion, where used, is soft metric conversion.

REFRIGERANT CONDENSERS

SECTION 23 63 00

PART 1 – GENERAL

3.03 SECTION INCLUDES

- A. Heat Pump Units

Specifier Note: Revise paragraph below to suit project requirements. Add section numbers and titles per CSI *MasterFormat* and specifier's practice.

1.2 RELATED SECTIONS

Specifier Note: Article below may be omitted when specifying manufacturer's proprietary products and recommended installation. Retain Reference Article when specifying products and installation by an industry reference standard. If retained, list standard(s) referenced in this section. Indicate issuing authority name, acronym, standard designation and title. Establish policy for indicating edition date of standard referenced. Conditions of the Contract or Division 1 References Section may establish the edition date of standards. This article does not require compliance with standard, but is merely a listing of references used. Article below should list only those industry standards referenced in this section. Retain only those reference standards to be used within the text of this Section. Add and delete as required for specific project.

1.3 REFERENCES

- A. Air-Conditioning and Refrigeration Institute (ARI):
 - 1. ARI 270-2008/370 Sound Rating of Outdoor Unitary Equipment
 - 2. ARI 340/360 Commercial and Industrial Unitary Air-Conditioning and Heat Pump Equipment (ANSI approved)
- B. All models meet DOE 2023 minimum efficiency standards
- C. Servicing Standards and Codes:
 - 1. National Electric Code (NEC)
 - 2. Underwriters Laboratories (UL)
 - 3. Underwriters Laboratories of Canada® (ULC)
 - 4. Canadian Electric Code (CEC)
- D. ISO 9001, units manufactured to quality standard
- E. Meet Minimum EPACT, and addendums, efficiency levels
- F. All models are ASHRAE 90. 1-2016 compliant
- G. ETL Listed

Specifier Note: Article below should be restricted to statements describing design or performance requirements and functional (not dimensional) tolerances of a complete system. Limit descriptions to composite and operational properties required to link components of a system together and to interface with other systems.

1.4 PERFORMANCE REQUIREMENTS

- A. Condensing Unit: [6, 7.5, 10-ton capacity]
- B. Electrical Characteristics:
 - 1. 60 Hz
 - 2. 3 phase
 - 3. Voltage: [208/230 V] [460 V] [575 V]

Specifier Note: Article below includes submittal of relevant data to be furnished by Contractor before, during or after construction. Coordinate this article with Architect's and Contractor's duties and responsibilities in Conditions of the Contract and Division 1 Submittal Procedures Section.

1.5 SUBMITTALS

- A. General: Submit listed submittals in accordance with Conditions of the Contract and Division 1 Submittal Procedures
- B. Product Data: Submit product data for specified products
- C. Shop Drawings:
 - 1. Submit shop drawings in accordance with Section [01 33 00 - Submittal Procedures]
 - 2. Indicate:
 - a. Equipment, piping and connections, together with valves, strainers, control assemblies, thermostatic controls, auxiliaries and hardware and recommended ancillaries which are mounted, wired and piped ready for final connection to building system, its size and recommended bypass connections
 - b. Piping, valves and fittings shipped loose showing final location in assembly
 - c. Control equipment shipped loose, showing final location in assembly
 - d. Field wiring diagrams
 - e. Dimensions, internal and external construction details, installation clearances, recommended method of installation, sizes and location of mounting bolt holes
 - f. Detailed composite wiring diagrams for control systems showing factory installed wiring and equipment on packaged equipment or required for controlling devices or ancillaries, accessories, controllers
- D. Quality Assurance:
 - 1. All units to be factory tested before shipping
 - 2. Certificates: Product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements
 - 3. Manufacturer's Instructions: Manufacturer's installation instructions

Specifier Note: Coordinate paragraph below with Part 3 Field Quality Requirements Article herein. Retain or delete as applicable.

- E. Closeout Submittals: Submit the following:
 - 1. Warranty: Warranty documents specified herein

2. Operation and Maintenance Data: Operation and maintenance data for installed products in accordance with Division 1 Closeout Submittals (Maintenance Data and Operation Data) Section. Include methods for maintaining installed products and precautions against cleaning materials and methods detrimental to finishes and performance. Include names and addresses of spare part suppliers
3. Provide brief description of unit, with details of function, operation, control and component service
4. Commissioning Report: Submit commissioning reports, report forms and schematics in accordance with Section [01 81 00 – Commissioning]

1.6 QUALITY ASSURANCE

- A. Qualifications:
 1. Installer experienced in performing work of this section who has specialized in installation of work similar to that required for this project
 2. Manufacturer Qualifications: Manufacturer capable of providing field service representation during construction and approving application method
 3. Preinstallation Meetings: Conduct preinstallation meeting to verify project requirements, manufacturer's installation instructions and manufacturer's warranty requirements. Comply with Division 1 Project Management and Coordination (Project Meetings).

1.7 DELIVERY, STORAGE & HANDLING

- A. General: Comply with Division 1 Product Requirements
- B. Ordering: Comply with manufacturer's ordering instructions and lead time requirements to avoid construction delays
- C. Packing, Shipping, Handling and Delivery:
 1. Deliver materials in manufacturer's original, unopened, undamaged containers with identification labels intact
 2. Ship, handle and unload units according to manufacturer's instructions
- D. Storage and Protection:
 1. Store materials protected from exposure to harmful weather conditions
 2. Factory shipping covers to remain in place until installation

Specifier Note: Coordinate article below with Conditions of the Contract and with Division 1 Closeout Submittals (Warranty).

1.8 WARRANTY

- A. Project Warranty: Refer to Conditions of the Contract for project warranty provisions
- B. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by authorized company official. Manufacturer's warranty is in addition to, and not a limitation of, other rights Owner may have under Contract Documents.

Specifier Note: Coordinate paragraph below with manufacturer's warranty requirements.

- C. Warranty: Commencing on Date of Installation.
 - 1. Compressor: 5 year limited (nonresidential applications)
 - 2. Other Covered Components: 1 year limited (nonresidential applications)

PART 2 PRODUCTS

Specifier Note: Retain article below for proprietary method specification. Add product attributes, performance characteristics, material standards and descriptions as applicable. Use of such phrases as “or equal” or “or approved equal” or similar phrases may cause ambiguity in specifications. Such phrases require verification (procedural, legal and regulatory) and assignment of responsibility for determining “or equal” products.

2.1 OUTDOOR CONDENSING UNITS

- A. Manufacturer: Lennox Industries
 - 1. Contact: 2140 Lake Park Blvd., Richardson, TX 75080; Telephone: (800) 453-6669;
Web site: www.lennoxcommercial.com
- B. Proprietary Products/Systems: ELKP Series, including the following equipment:
 - 1. Cabinet:
 - a. Interior Panels - G-90 Galvanized steel
 - b. Exterior Panels
 - 1. Framing members to be painted steel with a thickness of 18 or 20 ga.
 - 2. Doors and panels to be painted steel with a thickness of 20 or 22ga.
 - 3. G60 pre-painted, galvanized steel
 - 4. Textured pre-paint with Polyurethane finish
 - 5. Corrosion resistant paint
 - i. Cyclic fog and UV exposure up to 1680 hours
 - ii. Adhesion: ASTM D3359
 - iii. Impact resistance: ASTM D2794
 - iv. Humidity resistance: ASTM D2247
 - v. Abrasion resistance: ASTM 4060
 - vi. Heat resistance: ASTM D3454
 - vii. Flexibility: ASTM D4145 (NCCAI-19)
 - c. Based rails with fork slots both sides
 - d. Refrigerant line connections to be located outside the unit
 - e. Control access
 - 2. Compressor:
 - a. Scroll Type, 2-stage
 - b. Resiliently mounted on rubber mounts for vibration isolation
 - c. Overload protected
 - d. Internal excessive current and temperature protection
 - e. Crankcase heater
 - 3. Refrigerant System
 - a. General
 - 1. Refrigerant: R454-B

2. Fully serviceable liquid and suction line service valves
 3. Gauge ports
- b. Refrigerant System (large):
 1. High pressure switch
 2. Loss of charge (low pressure) switch
 3. Minimum run time control
 4. Hi-capacity driers
- c. 4-way reversing valve
4. Outdoor Coil(s):
 - a. Aluminum rippled and lanced fins
 - b. Copper tube construction
 - c. Aluminum fins to be mechanically bonded to copper tubes
 - d. All coils to be high pressure leak tested at factory
5. Outdoor Coil Fans/Air Mover:
 - a. Direct drive, propeller type fan(s)
 - b. Totally enclosed fan motors with rain shield
 - c. PVC coated steel fan guards
 - d. Fan service by removal of fan guard
6. Controls
 - a. All controls factory wired
 - b. Cooling – Low Ambient operation, standard down to 45 °F
 - c. Defrost control
 - d. All models use a single line voltage to 24VAC transformer mounted in the control box
7. [Field Installed Options/Accessories]:
 - a. Outdoor Coils:
 1. [Hail Guards: heavy duty metal mesh enclosures]
 2. [Coil Guards]
 - b. Controls
 1. [Low Ambient Control, down to 0 °F]
 - a. Pressure regulated fan speed control
 3. [Thermostat]
 4. [BACNet Integration]

2.2 PRODUCT SUBSTITUTIONS

A. Substitutions: No substitutions permitted

PART 3 EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

Specifier Note: Revise article below to suit project requirements and specifier's practice.

- A. Compliance: Comply with manufacturer's written data, including product technical bulletins, product catalog installation instructions and product carton installation instructions.

3.02 EXAMINATION

- A. Site Verification of Conditions: Verify substrate conditions, which have been previously installed under other sections, are acceptable for product installation in accordance with manufacturer's instructions.

3.03 INSTALLATION

Install Heat Pump Units in accordance with manufacturer's instructions and regulations of authorities having jurisdiction.

END OF SECTION